	1		2		
	FINISH SELECTIONS		FINISH SELECTIONS		
CARPET (CPT-X):		ACOUSTICAL CEILING TILE (ACT-X):			
(CPT-1) MANUFACTURER: COLLECTION: STYLE: COLOR:	INTERFACE EVENSONG SNOW MOON NOON MOON	(ACT-1) MANUFACTURER: STYLE: STYLE #: SIZE:	USG RADAR ILLUSION TWO/24 PANELS 2742 2' X 4'		
INSTALLATION: (CPT-2) MANUFACTURER:	VERTICAL ASHLAR INTERFACE	EDGE: COLOR: SUSPENSION SYS.:	SLT WHITE USG DONN BRAND DX/DXL 15/16"		
COLLECTION: STYLE: COLOR: LOCATION:	STEP REPEAT SR699 GRANITE VESTIBULE	(RS-1) MANUFACTURER: STYLE: COLOR:): HUNTER DOUGLAS E SCREEN 7510 CHARCOAL/GRAY		
LUXURY VINYL TIL (LVT-1) MANUFACTURER:	E (LVT-X): INTERFACE	OPENNESS: LOCATION: TRANSITION (TS-X):	10% ALL EXTERIOR WINDOWS		
STYLE: STYLE: SIZE:	STUDIO SET MUSHROOM 12" X 12"	(TS-1) (GENERAL) MANUFACTURER:	SCHLUTER SYSTEMS		
TILE (T-X): (T-1) (TYPICAL) MANUFACTURER:	OLYMPIA TILE	STYLE & SIZE: STYLE:	RENO-TK SIZE TO BE V.I.F. IN ACCORDANCE WITH MATERIAL(S) THICKNESS CLEAR SATIN ANODIZED		
DISTRIBUTOR: STYLE: COLOR: SIZE: INSTALLATION:	DOBKIN TILE OIKOS GRIGIO 12"X24" 1/3 BRICK LAY	LOCATION(S): NOTE(S):	ALUMINUM FLOORING MATERIAL CHANGES AS NECESSARY. PLEASE SEE GENERAL NOTES RE: TRANSITIONS		
GROUT: <u>TILE BASE (TB-X):</u>	FLEXTILE -	MISCELLANEOUS (MISC-1)(CHAIRAIL) SPECIES:	MAPLE		
(TB-1) (TYPICAL) MANUFACTURER: DISTRIBUTOR: STYLE:	OLYMPIA TILE DOBKIN TILE OIKOS	STAIN: SIZE: PROFILE: HEIGHT:	ST-1 4" TO BE SELECTED BY ARCH. VERIFY W/TENANT		
COLOR: SIZE: NOTE:	GRIGIO 4" TO BE USED WITH T-1	(MISC-2) (3-FORM) MANUFACTURER: STYLE: LOCATION:	3FORM SPIDER RECEPTION DESK FEATURES		
(RB-1) MANUFACTURER: COLOR:	JOHNSONITE PEBBLE 32				
LOCATION: MEDIUM DENSITY	OFFICE AREAS FIBREBOARD (MDF-X):				
(MDF-1) (TYPICAL) PROFILE: HEIGHT: COLOR:	TBD 4" P-3				
PAINT (P-X): (P-1) (TYPICAL) MANUFACTURER: NOTE: FINISH:	SHERWIN WILLIAMS MINDFUL GRAY SW7016 EGGSHELL				
(P-2) (ACCENT) MANUFACTURER: COLOR: FINISH:	SHERWIN WILLIAMS DOVETAIL SW7018 EGGSHELL				
(P-3) (ACCENT) MANUFACTURER: COLOR: FINISH:	SHERWIN WILLIAMS GULFSTREAM SW6768 EGGSHELL				
(P-4) (TRIM) MANUFACTURER: COLOR: FINISH:	SHERWIN WILLIAMS GAUNTLET GRAY SW7019 SEMI-GLOSS				
(P-5) (CHECK IN/CH MANUFACTURER: COLOR: FINISH:	ECK OUT SOFFIT) SHERWIN WILLIAMS CRUSHED ICE SW7647 FLAT				
STACKED STONE (STS-1)	<u>5TS-X):</u>				
MANUFACTURER: STYLE: COLOR: LOCATION:	CORONADO STONE PROLEDGE HURON RECEPTION				
WOOD VENEER (W (WV-1)	V-X):				
SPECIES: STAIN: LOCATION: STAIN (ST-X):	MAPLE ST-1 RECEPTION DESK				
(ST-1) STAIN: PLASTIC LAMINAT	TO MATCH SAMPLE PROV. BY ARCH				
(PL-1) (TYPICAL) MANUFACTURER: COLOR:	NEVAMAR GIANT GRAY BAMBOO WX1150-PV				
(PL-2) (TYPICAL COUMANUFACTURER: COLOR:	NEVAMAR EISKAFFE				
MANUFACTURER: COLOR: SOLID SURFACE (SS	NEVAMAR KOPI SUSU LN6002T				
(SS-1) MANUFACTURER: COLLECTION: FINISH: LOCATION: DOORS (WD-X):	WILSONART QUARTZ SELECT PAPER LANTERN Q6001 RECEPTION DESK TRANSACTION				
(WD-1) MANUFACTURER: SPECIES: FINISH:	MASONITE MAPLE STOUT				

ROOM FINISH SCHEDULE - FIRST FLOOR									
ROOM NUMBER	ROOM NAME	BASE	FLOOR	WALLS	MILLWORK		CEILINIC		
					CABINET/ SHROUD	COUNTERTOP/ BACKSPLASH	CEILING HEIGHT	REMARKS	
101	WAITING	TB-1	T-1	P-1/P-2			10'-6"	1	
102	RECEPTION	MDF-1	LVT-1	P-1/P-2			10'		
103	PRIVATE CHECK IN	RB-1	CPT-1	P-1			9'-0"		
104	SECURITY	MDF-1	LVT-1/CPT-1	EXISTING			EXISTING	2	
105	COFFEE	RB-1	CPT-1						

ROOM FINISH LEGEND						
FLOORS	WALLS					
CPT = CARPET	P = PAINT					
T = TILE	WT = WALL TILE					
LUXURY VINYL TILE = LVT	STS = STACKED STONE					
BASE	MISCELLANEOUS					
RB = RUBBER BASE	SS = SOLID SURFACE					
TB - TILE BASE	PL = PLASTIC LAMINATE					
RB = RUBBER BASE	TS = TRANSITION STRIP					
MDF = MEDIUM DENSITY FIBREBOARD	RS = ROLLER SHADES					
CEILING	ST = STAIN					
ACT = ACOUSTIC CEILING TILE	WV = WOOD VENEER					
GYP = GYPSUM BOARD	MISC = MISCELLANEOUS					
DOORS	MATERIALS					
WD = WOOD DOOR	P.B. = PARTICLE BOARD					

REMARKS

GYP. = GYPSUM BOARD

1. REFER TO REFLECTED CEILING PLAN FOR EXACT DETAILS (MATERIALS, HEIGHTS, SIZES, ETC...) FOR CEILING LAYOUT.

2. CONTACT ARCHITECT FOR CARPET PATTERN INSTALLATION GUIDE.

3. ADD CHAIR RAIL WHERE SPECIFIED. CONFERENCE ROOM TO RECEIVE CHAIR RAIL ON ALL WALLS WITH THE EXCEPTION

4. CHECK IN SIDE OF DESK TO RECEIVE WOOD BASE, NOT MDF. MDF TO BE USED BEHIND DESK AND THROUGHOUT

5. SOFFIT AT CHECK IN/CHECK OUT TO BE PAINTED P-5.

6. NO THRESHOLD NECESSARY AT CPT-1 INSET IN LVT-1.

GENERAL NOTES

 ANY AND ALL FINISH SELECTIONS/ COLORS MUST BE SUBMITTED TO ARCHITECT FOR APPROVAL ACCOUNTING FOR PROPER LEAD TIME. ANY FINISH THAT IS INSTALLED WITHOUT ARCHITECTS APPROVAL MAY BE REQUIRED TO BE REMOVED AND REPLACED BY THE GENERAL CONTRACTOR. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ORDER ALL MATERIALS AT THE APPROPRIATE TIME. ANY FEE'S INCURRED AS A RESULT OF FINISHES NOT BEING ORDERED ON TIME WILL BE THE RESPONSIBILITY OF THE CONTRACTOR.

• ANY DISCREPANCIES BETWEEN ARCHITECTURAL ELEVATION(S), PLAN(S), SCHEDULE(S) AND NOTES MUST BE BROUGHT TO ARCHITECTS ATTENTION. ARCHITECT MUST BE CONTACTED AND GIVE APPROVAL TO MOVE FORWARD WITH SPECIFIC DIRECTION PRIOR TO ANTICIPATED ACTION.

- ALL INTERIOR PRODUCTS TO MEET/EXCEED FLAME SPREAD RATING PER CODE
- ALL FLOOR FINISHES TO EXTEND BENEATH ALL MILLWORK.

ALL ELECTRICAL PANEL COVERS AND/OR MECHANICAL EQUIPMENT AND/OR DUCTING TO BE PAINTED TO

 ANY CEILING HVAC SUPPLY/DIFFUSERS ETC. TO BE PAINTED TO MATCH SURROUNDING CEILING FINISH. ANY QUESTIONS OR CONCERN TO BE BROUGHT TO ARCHITECT'S ATTENTION FOR FINAL DECISION PRIOR TO ORDER/INSTALL BY CONTRACTOR OR OTHER.

- ALL GYPSUM BOARD CEILINGS TO BE PAINTED IN A FLAT WHITE FINISH UNLESS SPECIFIED.
- ALL EXPOSED MECHANICAL DUCT COVERS SHALL BE PAINTED TO MATCH THE SURROUNDING WALL/ CEILING COLOR. PRIME AS NECESSARY

 PROVIDE (1) COAT WALL PRIMER FOLLOWED BY (2) COATS WALL PAINT ON ALL INTERIOR WALL SURFACE UNLESS OTHERWISE NOTED IN SPECIFICATIONS. SEE SPEC FOR DETAILS.

• WHERE DARK PAINT COLORS ARE APPLIED, USE DEEP GRAY BASE PRIMER TO PREVENT BURNISHING.

• CHAIR RAIL HEIGHT TO BE DECIDED BY OWNER. STAIN ST-1 WHERE SPECIFIED ON A-603.

 NO CHANGES OR SUBSTITUTIONS WILL BE MADE TO THE FOLLOWING FINISHES UNLESS DIRECTED BY THE OWNER OR ARCHITECT.

• CONTRACTOR TO PROVIDE (TS-1) AT ALL FLOORING MATERIAL CHANGES NEEDING THRESHOLDS. NECESSARY SIZES TO BE DETERMINED BY CONTRACTOR AND V.I.F. BASED ON MATERIAL THICKNESS. NO THRESHOLD NECESSARY AT CPT-1 INSET IN LVT-1.

 PROVIDE CLEAR BEAD OF SILICONE OR CLEAR CALK TO SEAL BETWEEN MILLWORK PIECES(IE: COUNTER TOP AND BACKSPLASH) AND MILLWORK AND WALL. (TYPICAL).

• ALL COLOR SELECTION OF PLASTIC LAMINATE SUPPORTS TO MATCH ADJACENT WALL.

• USE MDF-1 BASE AT WAITING ROOM. PLEASE SUBMIT PROFILE OPTIONS TO ARCHITECT FOR APPROVAL.

WINDOWS:

ALL GLAZING FACING EXTERIOR TO RECEIVE RS-1. ALL WINDOW SILLS TO BE PL-2.

DOORS:

• ALL HOLLOW METAL DOOR FRAMES TO BE PAINTED WITH P-4.

OUTLETS:

• ALL OUTLET SWITCHES AND COVERS TO BE WHITE.

• SIGNAGE LOCATIONS WILL NEED TO BE PROVIDED AND INSTALLED BY CONTRACTOR. TO BE SELECTED AND APPROVED BY ARCHITECT AND CLIENT PRIOR TO MANUFACTURER/PURCHASE TO BE PROVIDED BY TAKEFORM.

Services

Endeavor Health

NOTICE

This document, the property of, prepared and issued by the architect, is submitted for the specific project namely <u>Endeavor Health Services</u> and the recipient by accepting this document assumes custody and agrees that this document will not be copied or reproduced in part or in whole, and any special features peculiar to this design shall not be incorporated in any other project, unless prior agreement has been obtained in writing. These documents will be returned immediately upon completion of the project or upon the request of the architect.

This document is the exclusive property of the architect, no rights to ownership are transferable, or shall be lost by the filing of this document with any

and all public authorities for the purpose of compliance with Codes and or Ordinances,

i.e. Building Permit, etc.

1131 Broadway Buffalo, NY

05-22-18: ISSUED FOR BID/PERMIT

SA PROJECT TEAM: PRINCIPAL P.Silvestri

PROJ. ARCH. _____ DRAFTER ___

JOB CAPT. _____ INTERIORS _

TITLE:

ROOM FINISH SCHEDULE & GENERAL NOTES



SA JOB #: 14121.01

DATE: 05-22-18