FINISH SELECTIONS

CARPET (CPT-X):

(CPT-1)
MANUFACTURER: PATCRAFT
STYLE: VIVID 10302
COLOR: FLASH
SIZE: 24" X 24"
LOCATION: TYPICAL
INSTALLATION: HERRINGBONE

ROLLER SHADES (RS-X)

(RS-1)
MANUFACTURER: HUNTER DOUGLAS
SERIES: ROLLER SHADE 10% OPENESS FACTOR
COLOR: CHARCOAL/ BRONZE
LOCATION: ALL EXTERIOR WINDOWS EXCEPT WHERE OTHERWISE CALLED OUT.

(RS-2)
MANUFACTURER: HUNTER DOUGLAS
SERIES: BLACK-OUT SCREEN
COLOR: 3006 CHARCOAL/ BRONZE
LOCATION: EXAM ROOMS 111 AND 115

WALL COVERING (WC):

(WC-1)
MANUFACTURER: ARC COM
TYPE: ACW-51414
COLOR: CINNABAR #24
LOCATION: BEHIND RECEPTION DESK

MISCELLANEOUS:
(WALK OFF MAT)-MISC. 1

MANUF: PHILADELPHIA
STYLE: SUCCESSION II
COLOR: 00702 WOOD SMOKE

TILE:
MANUF: DOBKIN
STYLE: YURA
COLOR: WHITE
SIZE: 12"X12"

FINISH SELECTIONS

RUBBER BASE (RB):

(RB-1)
MANUFACTURER: ROPPE
COLOR: 125 FIG

WALL PROTECTION (WP):

(WP-1)
MANUF: INPRO
STYLE: RIGID VINYL SHEET
SIZE: 48" H.
COLOR: BISCOTTI
LOCATION: INTAKE

PAINT (P):

(P-1)
(TYPICAL & RECEPTION ,CORRIDORS...)
MANUFACTURER: SHERWIN WILLIAMS
COLOR: INTERACTIVE CREAM #FN114
FINISH: EGGSHELL

(P-2)
(CORRIDOR ACCENT & EXAM ACCENT)
MANUFACTURER: BENJAMIN MOORE
COLOR: 2096 ADIRONDACK BROWN
FINISH: EGGSHELL

(P-3)
(EXAM ROOM /OFFICES... PAINT)
MANUFACTURER: BENJAMIN MOORE
COLOR: HC 86 KINGSPORT GRAY
FINISH: EGGSHELL

(P-4)
(DOOR TRIM)
MANUFACTURER: BENJAMIN MOORE
COLOR: BROWN SUGAR 2112-20
FINISH: EGGSHELL

PLASTIC LAMINATE (PL):

(PL-1)
MANUFACTURER: PANOLAM
COLOR: WM791 HARDROCK MAPLE
LOCATION: EXAM & RESTROOM CABINETS/ RECEPTION MAIN

(PL-2)
MANUFACTURER: PIONITE
COLOR: AT391 PHOENIX
FINISH: SUEDE
LOCATION: COUNTER TOP

FINISH SELECTIONS

WOOD DOORS (WD):

(WD-1)
MANUFACTURER: IF NEW DOORS ARE NEEDED MATCH THE EXISTING

ACOUSTICAL CEILING TILE (ACT):

(ACT-1)
MANUFACTURER: USG
TYPE: RADAR ILLUSION TWO/24 PANELS
EDGE PROFILE: SLT
SIZE: 2' X 4' (SCORED 2' X 2')
STYLE: 2742
COLOR: WHITE

SOLID SURFACE (SS-X):

(SS-2) (RECEPTION COUNTER TOP)
MANUFACTURER: AVONITE
COLOR: DAKOTA RUST K3-1900
FINISH: GLOSS

GENERAL NOTES

- NO CHANGES OR SUBSTITUTIONS WILL BE MADE TO THE FOLLOWING FINISHES UNLESS DIRECTED BY THE OWNER OR ARCHITECT.
- MANY FINISH MATERIALS REQUIRE A SUBSTANTIAL LEAD TIME. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ORDER ALL MATERIALS AT THE APPROPRIATE TIME. ANY FEES INCURRED AS A RESULT OF FINISHES NOT BEING ORDERED ON TIME WILL BE THE RESPONSIBILITY OF THE CONTRACTOR.

GENERAL NOTES CONT.

- ANY AND ALL FINISH SELECTIONS/ COLORS MUST BE SUBMITTED TO ARCHITECT FOR APPROVAL ACCOUNTING FOR PROPER LEAD TIME. ANY FINISH THAT IS INSTALLED WITHOUT ARCHITECTS APPROVAL MAY BE REQUIRED TO BE REMOVED AND REPLACED BY THE GENERAL CONTRACTOR.
- ALL FLOOR FINISHES TO EXTEND BENEATH ALL MILLWORK.

CEILINGS:

- ALL GYPSUM BOARD CEILINGS AND GYPSUM BOARD SOFFITS TO BE PAINTED IN A FLAT WHITE FINISH UNLESS SPECIFIED.
- ALL EXPOSED MECHANICAL DUCT COVERS SHALL BE PAINTED TO MATCH THE SURROUNDING WALL/ CEILING COLOR. PRIME AS NECESSARY.

WALLS:

- PROVIDE (1) COAT WALL PRIMER FOLLOWED BY (2) COATS WALL PAINT ON ALL INTERIOR WALL SURFACE UNLESS OTHERWISE NOTED IN SPECIFICATIONS. SEE SPEC FOR DETAILS.

FLOORS:

- PROVIDE MARBLE THRESHOLD AT ALL TOILET ROOM TRANSITIONS. ARCHITECT TO CHOOSE FROM MANUFACTURER FULL RANGE OF COLORS.
- KEEP EXISTING TILE IN TOILET ROOMS AND CLEAN EXISTING GROUT
- PROVIDE RUBBER THRESHOLDS, (TS-1), AT ALL OTHER FLOOR MATERIAL CHANGES AND THRESHOLDS.

ROOM FINISH SCHEDULE

ROOM NUMBER	ROOM NAME	BASE	FLOOR	FLOOR GROUT	WALLS	WALL GROUT	MILLWORK		CEILING		REMARKS
							FACE CABINET/ SHROUD	COUNTER TOP/ APRON/ BACKSPLASH	MATL	HEIGHTS	
101	VESTIBULE	TILE	MISC-1/TILE	GR-1	GYP /P-1				GYP	EXISTING	KEEP EXISTING CHAIR RAIL
102	WAITING	EXISTING WD	CPT-1		GYP/P-1, P-2				ACT-1/ GYP	EXISTING	
103	WAITING	EXISTING WD	CPT-1		GYP/WC-1/P-1				ACT-1/ GYP	EXISTING	
104	WAITING	EXISTING WD	CPT-1		GYP/P-1				EXT	EXISTING	
105	RECEPTION	EXISTING WD	CPT-1		GYP/WC-1/ P-1		WD	SS-1	ACT-2/ GYP	EXISTING	
106	OPTICAL AREA	RB-1	CPT-1		GYP/P-1				ACT-1	EXISTING	
107	LAB	RB-1	EXISTING		GYP/P-1				ACT-1	EXISTING	
108	SURGEON SCHEDULING	RB-1	CPT-1		GYP/P-3				ACT-1	EXISTING	
109	CORRIDOR	WD	CPT-1		GYP/P-1, P-3				ACT-1	EXISTING	
110	MGR. OFFICE	RB-1	CPT-1		GYP/P-3				ACT-1	EXISTING	
111	IMAGING	RB-1	CPT-1		GYP/P-3		PL-1	PL-2	GYP	EXISTING	
112	IMAGING	RB-1	CPT-1		GYP/P-1		PL-1	PL-2	ACT-1	EXISTING	
113	MECHANICAL	RB-1	EXISTING		EXISTING				ACT-1	EXISTING	
114	EXAM	RB-1	CPT-1		GYP/P-3, P-2		PL-1	PL-2	ACT-1	EXISTING	
115	EXAM	RB-1	CPT-1		GYP/P-3, P-2		PL-1	PL-2	ACT-1	EXISTING	
116	CONTACT LENSE	RB-1	CPT-1		GYP/P-1		PL-1	PL-2	ACT-1	EXISTING	
117	TESTING	RB-1	VCT-1		GYP/P-3		PL-1	PL-2	ACT-1	EXISTING	
118	EXAM	RB-1	CPT-1		GYP/P-3, P-2		PL-1	PL-2	ACT-1	EXISTING	
119	EXAM	RB-1	CPT-1		GYP/P-3, P-2				ACT-1	EXISTING	
120	PATIENT TOILET	EXISTING	EXISTING		GYP/P-1				ACT-1	EXISTING	
121	EXAM	RB-1	CPT-1		GYP/ P-3, P-2		PL-1	PL-2	ACT-1	EXISTING	
122	DIALTION	RB-1	CPT-1		GYP/ P-3, P-2		PL-1	PL-2	ACT-1	EXISTING	
123	EXAM	RB-1	CPT-1		GYP/ P-3, P-2		PL-1	PL-2	ACT-1	EXISTING	
124	CORRIDOR	RB-1	CPT-1		GYP/ P-1, P-3				ACT-1	EXISTING	
125	EXAM	RB-1	CPT-1		GYP/ P-3, P-2		PL-1	PL-2	ACT-1	EXISTING	
126	EXAM	RB-1	CPT-1		GYP/ P-3, P-2		EXISTING	EXISTING	ACT-1	EXISTING	
127	TECH.	RB-1	CPT-1		GYP/ P-1		PL-1	PL-2	ACT-1	EXISTING	
128	PRIVATE TOILET	EXISTING	EXISTING		GYP/ P-3				ACT-1	EXISTING	
129	PHYSICIAN'S OFFICE	RB-1	CPT-1		GYP/ P-3				ACT-1	EXISTING	
130	INTAKE	RB-1	CPT-1		GYP/CR-1/P-3		PL-1	PL-2	ACT-1	9'-0"	
131	INTAKE	RB-1	CPT-1		GYP/CR-1/P-3		PL-1	PL-2	ACT-1	9'-0"	
132	CORRIDOR	RB-1	CPT-1		GYP/ P-1, P-3				ACT-1	`	
133	PRE-SCREEN	RB-1	CPT-1		GYP/ P-3		PL-1	PL-2	ACT-1	EXISTING	
134	INTAKE	RB-1	CPT-1		GYP/ CR-1/P-3		PL-1	PL-2	ACT-1	EXISTING	
135	INTAKE	RB-1	CPT-1		GYP/ CR-1/P-3		PL-1	PL-2	ACT-1	EXISTING	
136	INTAKE	RB-1	CPT-1		GYP/ CR-1/P-3		PL-1	PL-2	ACT-1	EXISTING	
137	INTAKE	RB-1	CPT-1		GYP/ CR-1/P-3		PL-1	PL-2	ACT-1	EXISTING	
138	BUSINESS OFFICE	RB-1	CPT-1		GYP/P-3				ACT-1	EXISTING	
139	COMPUTER	RB-1	CPT-1		GYP/ P-1				ACT-1	EXISTING	
140	VF OFFICE	RB-1	CPT-1		GYP/ P-1				ACT-1	9'-0"	
141	CORRIDOR	RB-1	CPT-1		GYP/P-1				ACT-1	EXISTING	
142	EPIC ROOM	RB-1	CPT-1		GYP/P-3				ACT-1	EXISTING	
143	CLOSET	RB-1	EXISTING		GYP/P-3				ACT-1	EXISTING	
144	NOT USED									EXISTING	
145	STAFF TOILET	EXISTING	EXISTING		GYP/P-3				ACT-1	EXISTING	
146	H.C. TOILET	EXISTING	EXISTING		GYP/P-3				ACT-1	EXISTING	
147	CLOSET	RB-1	CPT-1		GYP/P-1				ACT-1	EXISTING	
148	VF ROOM	RB-1	CPT-1		GYP/P-1				ACT-1	EXISTING	

ROOM FINISH LEGEND

FLOORS
- T = CERAMIC TILE
- CPT = CARPET
- VCT = VINYL COMPOSITE TILE
- EXTC = EXISTING CONCRETE

BASE
- TB = CERAMIC TILE BASE
- RB= RUBBER BASE
- EXT = EXISTING
- CPTB = CARPET BASE

WALLS
- P = PAINT
- WC = WALL COVERING
- WT = WALL TILE

CEILING
- ACT = ACOUSTIC CEILING TILE
- GYP = GYPSUM BOARD
- EXP = EXPOSED CEILING

MISCELLANEOUS
- PL = PLASTIC LAMINATE
- FRP= FIBER REINFORCED POLYMER
- CH = CHAIR RAIL
- SS = SOLID SURFACE

MATERIALS
- P.B. = PARTICLE BOARD
- GYP. = GYPSUM BOARD

N O T I C E

This document, the property of, prepared and issued by the architect, is submitted for the specific project namely _____ and the recipient by accepting this document assumes custody and agrees that this document will not be copied or reproduced in part or in whole, and any special features peculiar to this design shall not be incorporated in any other project, unless prior agreement has been obtained in writing.These documents will be returned immediately upon completion of the project or upon the request of the architect.
This document is the exclusive property of the architect, no rights to ownership are transferable, or shall be lost by the filing of this document with any and all public authorities for the purpose of compliance with Codes and or Ordinances, i.e. Building Permit, etc.

Construction Services
Group of Upstate NY, Inc

2455 Wehrle Drive
Williamsville, NY 14221
Tel: (716) 633-4308 Fax: (716) 633-2656

Ross Eye Institute

301 Sterling Drive
Sterling Medical Park
Orchard Park, NY

ISSUE:

SA PROJECT TEAM: PRINCIPAL P.Silvestri
PROJ. ARCH. _____ DRAFTER _____
JOB CAPT. _____ INTERIORS _____

SEAL:

TITLE:

FINISH SCHEDULE

SILVESTRI
ARCHITECTS ▸ PC
1321 MILLERSPORT HWY PH. 716.691.0900
AMHERST, NY 14221 FAX 716.691.4773

SA JOB #: 12148

DATE: 1-3-14

DRAWING #: A-602