

M MUSSACHIO ARCHITECTS

30 NORTH FOREST ROAD
WILLIAMSVILLE, NEW YORK 14221
(716) 631-9949 FAX: 631-0521
anthony@mussachioarchitects.com

MARC C. MUSSACHIO, R.A.
ANTHONY C. MUSSACHIO, R.A.

ISLAMIC CENTER EXPANSION-PHASE 1

Arch. Job #218024

ADDENDUM NO. 3

April 29, 2019

This Addendum forms a part of and modifies the bidding and contract documents of the Project referenced herein. Please acknowledge receipt of this Addendum on Bid Form. Where any original item called for in the Project Manual or indicated on the Drawings is supplemented hereby, the supplemental requirements shall be considered as added thereto. Where any original item is amended, void, or supplemented hereby, the other provisions of such items not specifically amended, voided, or supplemented shall remain in effect.

The Drawings and Specifications dated April 12, 2019 for the Islamic Center Expansion are amended in the following particulars only.

A. GENERAL:

1. The Project has been loaded to Dodge Reports.

B. SPECIFICATION:

1. Replace Section 08 01 40, Entrances with the attached Section.
2. Replace Section 08 71 00, Door Hardware with the attached Section.
3. Replace Section 08 81 40, Glass & Glazing with the attached Section.

C. DRAWINGS:

1. C-102, SITE PLAN-LANDSCAPING - Regarding notes referring to "Any previously disturbed areas beyond the proposed parking lots to be seed". This shall be interpreted as grading and placing a minimum of 4" of clean, fresh topsoil and seed:

LAWN SEED

- 1) General: Seed shall be fresh, clean, new crop, delivered in original packages, unopened and bearing the guaranteed analysis.
- 2) Seed Mixtures:

	Proportion By Weight	Min. Purity	Min. Germination	Lbs./1000 sq.ft.
Type 1 - For General Lawn Use				
a) Bensun (A34) KY Bluegrass	25%	90%	85%	1.5
b) Penn Lawn Red Fescue	67%	95%	80%	4.0
c) Manhattan Perennial Rye	8%	95%	90%	<u>.5</u>
				6.0

- 3) Topsoil and seed shall extend up to 50'-0" beyond pavement or new work. All existing soil, beyond 50'-0" will be scratched and seeded only with intent of extending lawn to existing perimeter or scrub area.

2. Replace Drawing A-800, Door & window Schedule with the attached drawing dated R 4/29/19 where in the Door Schedule itself was revised to coordinate with the Specification Section referenced in this Addendum.